

#### **UOW SAFE@WORK**

# Roof Safety Survey BUILDING 2

Version 4



### **Contents**

1	Introduction	3
2	Purpose	3
3	Disclaimer	3
4	Roof Area Aerial Photo Zone Layout	
5	Risk Management	
	5.1 Risk Matrix	
	5.2 Risk Control	
	5.3 Contractors Risk Assessment	
6	Roof Safety Survey Building 2	
	6.1 Building 2 General Information	
	6.2 Building 2 Safety Systems Aerial Photo Layout	
	6.3 Building 2 Roof Photos	
7	Program Evaluation	
8	Related Documents	11
9	References	11
	9.1 Legislation	11
	9.2 Australian Standards	
	9.3 Codes of Practice	11
10	Version Control Table	

## 1 Introduction

The following document outlines the Roof Safety Survey (RSS) for Building 2 of the University of Wollongong located at Wollongong Campus Northfields Avenue Wollongong NSW 2522.

## 2 Purpose


This RSS is to be used as a general guideline to provide awareness and control measures for site personnel and contractors when accessing various roof areas. Personnel must make an assessment prior to accessing the roof. Should there be any potential for falls, all personnel must ensure the necessary fall prevention systems are utilised and operated in a "fall restraint" working mode. All ends users of Fall arrest equipment must be trained to a level of national recognition. All work practices and systems operations must be identified and documented in the risk assessment and safe work method statement.

## 3 Disclaimer

This document should be used as a general guide for roof access purposes only. Items detailed within this document were in situ at the time of inspection and may change. End users must use caution and evaluate the conditions as suitable to themselves.

Riverlands Roofing and Waterproofing (Louey Models Pty Ltd) accepts no responsibility for the actions of persons accessing these areas and or legislative compliance of fittings and fixtures of the site.

# 4 Roof Area Aerial Photo Zone Layout



Main Roof


Highlighted Zone Areas

Main Roof Access Door

# 5 Risk Management

#### 5.1 Risk Matrix

This risk assessment matrix below must be used reviewing in context with the University's <u>Risk Management Guidelines</u>.



#### 5.2 Risk Control

Risk control is a method of managing the risk with the primary emphasis on controlling the hazards at source. For a risk that is assessed as "high", steps should be taken immediately to minimize risk of injury. The method of ensuring that risks are controlled effectively is by using the "hierarchy of controls".

The Hierarchy of Controls are:

Order No.	<b>Control Type</b>	e Example		
Firstly	Eliminate	Removing the hazard, eg taking a hazardous piece of equipment out of service.		
Secondly	Substitute	Replacing a hazardous substance or process with a less hazardous one, eg substituting a hazardous substance with a non-hazardous substance.		
Thirdly	Isolation	Isolating the hazard from the person at risk, eg using a guard or barrier.		
Fourthly	Engineering	Redesign a process or piece of equipment to make it less hazardous.		
Fifthly	Administrative	Adopting safe work practices or providing appropriate training, instruction or information.		
Sixthly	Personal protective equipment	The use of personal protective equipment could include using gloves, glasses, earmuffs, aprons, safety footwear, dust masks.		

For more information on risk management visit:

https://www.uow.edu.au/about/services/safe-at-work/whs-framework

#### 5.3 Contractors Risk Assessment

The below tables have been populated by the University with known hazards that may be applicable for roof work.

All contractors are required to establish their own risk assessment and SWP/SWMS/etc specific to each task they perform, taking into account hazards that may not have been identified by the University.

Assess	Assessment of Hazards						
	Description of Activity/ Service Item	Description of Hazard (What has potential to cause injury or	Current Controls  (What is in place today that controls the risk? List any control measures	Risk rating (With <u>current</u> controls in place)			
		damage to property/environment?)	already implemented)	Consequence	Likelihood	Risk	

Risk Control							
Hazard No.	Additional Control Description (What should be done in the future to control the	Control Type (Elimination, Substitution, Isolation, Engineering,	Person Responsible	Risk rating (With <u>additional</u> controls in place)			
e Z	risk? What can be done to eliminate or further reduce the risk?)	Administration, PPE)		Consequence	Likelihood	Risk	

# 6 Roof Safety Survey Building 2

## 6.1 Building 2 General Information

Note: Before commencing any work obtain Roof Permit from Facilities Management Division Building:

University of Wollongong Campus Building 2

## **Description:**

Building 2 is a multi-storey building with a flat concrete roof surface that has a large number of services include air conditioning units, exposed pipe work roof ventilation ducts, antenna, fume cupboards and cooling tower with chemical hazards.

• Building 2 is also the access point for Building 4.

## SafetyNet Risk Assessment Reference Number:

UOW01886

#### Roof Access:

#### **Main Roof Access:**

• Access to the building's roof area is via the internal stairwell. Building 2's roof access door is located at the top of the stairwell (western facing).

## Signage:

Various restricted areas

## Compliance Plates:

No systems are on this building

## Height of Building:

Multi storey

#### Pitch:

< 5 degrees</p>

#### **Roof Construction:**

Concrete construction

## **Structural Integrity:**

Sound

## Vegetation:

• Yes (Western & Southern side have trees growing over the roof area)

## Fall Arrest System:

System	Certification Status	Certification By
Various Anchor Points	N/A	N/A
Horizontal Lifelines	N/A	N/A

(End users must follow manufacturer's instructions and use compatible attachments)

Services:		
<b>⊠</b> Gutters		☐ Fiberglass Skylights
A/C Units	☐ Telco Towers	⊠ Pipework
□ Ducts	Satellite Dishes	Cooling Tower
Roof Ventilators	Antenna	Roof Top Solar Panels
Existing Safety Systems:		
Horizontal Lifelines	☐ Vertical Lifelines	⊠ Walkway
Anchor Points		Parapets

## Work Activity & Frequency:

- Clean gutters/routine maintenance 6 months
- Service A/C plant- monthly

## 6.2 Building 2 Safety Systems Aerial Photo Layout

The following aerial photo indicates access points and safety systems layout.



#### **Legend:**

MA Main Roof Access Door




Cooling Tower Chemical Hazard

FL Fixed Ladder (Access to Building 4)

## 6.3 Building 2 Roof Photos

#### Main Roof



Building 2 internal staircase



Building 2 roof access door located at the top of the buildings internal staircase




Building 2 roof area with cooling tower chemical storage



Building 2 roof area with ducts and cooling tower and walkway



Building 2 roof area with fume cuboards



Building 2 roof area with



Building 2 roof area with exposed pipework & services



Building 2 roof area with ducts and exposed pipework



Building 2 roof area with fixed ladder access to Building 4

# **Program Evaluation**

Conditions that might warrant a review of the guidelines on a more frequent basis would include:

- changes to the roof
- change in the relevant legislation or Australian Standards
- organisational needs or WHS Committee concern.

#### 8 Related Documents

- Managing the Risk of Falls Guidelines
- Working at Heights Rescue Plan
- Roof Access Permit
- Roof Access Procedure

## References

#### 9.1 Legislation

- NSW Work Health and Safety Regulation 2017 Part 4.4 Falls
- NSW Public Health Regulation 2012
- Public Health Amendment (Legionella Control) Regulation 2018

#### 9.2 Australian Standards

- AS 1657: Fixed platforms, walkways, stairways and ladders Design, construction and installation
- AS 1891.1: Industrial fall-arrest systems and devices Harnesses and ancillary equipment
- AS 1891.2: Industrial fall-arrest systems and devices Horizontal lifeline and rail systems
- AS 1891.3: Industrial fall-arrest systems and devices Fall-arrest devices
- AS 1891.4: Industrial fall-arrest systems and devices Selection, use and maintenance
- AS 2210.1: Safety, protective and occupational footwear Guide to selection, care and use
- AS 3666: Air-handling & Water Systems for Buildings Microbial Control
- AS 4994.1: Temporary edge protection General requirements
- AS 4994.2: Temporary edge protection Roof edge protection Installation and dismantling
- AS 2550.10: Crane, Hoists and lifting equipment, section 5.9

#### Codes of Practice 9.3

- Managing the Risk of Falls at Workplaces (SafeWork NSW)
- NSW Guidelines for Legionella Control in Cooling Water Systems

#### 10 Version Control Table

Version Control	Date Released	Approved By	Amendment
1	November 2012	Manager WHS	New document
2	February 2014	Manager WHS	Standards update and re-certification review
3	January 2018	Manager WHS	Scheduled review. No changes required.
4	October 2020	Manager WHS	Document recreated by GO from Riverlands Roofing. All information reviewed/updated.